



C&I and Public Sector Prescriptive Program Impact Evaluation Report

Energy Efficiency Plan: Plan Year 2018
(1/1/2018-12/31/2018)

Presented to
Peoples Gas and North Shore Gas

Draft

April 17, 2019

Prepared by:

Karl Walter
Consultant
415.356.7101
karl.walter@navigant.com

Charles Ampong
Managing Consultant
608.497.2336
charles.ampong@navigant.com

www.navigant.com

Submitted to:

Peoples Gas
North Shore Gas
200 East Randolph Street
Chicago, IL 60601

Submitted by:

Navigant Consulting, Inc.
150 North Riverside
Suite 2100
Chicago, IL 60606
Phone 312.583.5700

Contact:

Randy Gunn
Managing Director
312.583.5714
randy.gunn@navigant.com

Kevin Grabner
Associate Director
608.497.2323
kevin.grabner@navigant.com

Robert Neumann
Associate Director
312.583.2176
rob.neumann@navigant.com

Disclaimer: This report was prepared by Navigant Consulting, Inc. ("Navigant") for Peoples Gas Light and Coke Company ("PGL") and North Shore Gas Company ("NSG") based upon information provided by PGL and NSG and from other sources. Use of this report by any other party for whatever purpose should not, and does not, absolve such party from using due diligence in verifying the report's contents. Neither Navigant nor any of its subsidiaries or affiliates assumes any liability or duty of care to such parties, and hereby disclaims any such liability.

TABLE OF CONTENTS

1. Introduction 1

2. Program Description 1

3. Program Savings Summary 4

4. Program Savings by Measure 5

5. Impact Analysis Findings and Recommendations 7

 5.1 Impact Parameter Estimates 7

 5.2 Other Findings and Recommendations 7

6. Appendix 1. Impact Analysis Methodology 10

7. Appendix 2. Program-Specific Inputs for the Illinois TRC 12

LIST OF TABLES AND FIGURES

Table 2-1. 2018 Volumetric Summary for PGL 1

Table 2-2. 2018 Installed Measure Quantities for PGL 2

Table 2-3. 2018 Volumetric Summary for NSG 2

Table 2-4. 2018 Installed Measure Quantities for NSG 3

Table 3-1. 2018 Annual Energy Savings Summary for PGL 4

Table 3-2. 2018 Annual Energy Savings Summary for NSG 4

Table 4-1. 2018 Annual Energy Savings by Measure for PGL 5

Table 4-2. 2018 Annual Energy Savings by Measure for NSG 6

Table 5-1. Verified Gross Savings Parameters 7

Table 5-2. Historical Realization Rates and NTG Values – C&I 9

Table 5-3. Historical Realization Rates and NTG Values – Public Sector 9

Table 6-1. Measure-Level Gross Realization Rate Estimates for Steam Traps 10

Table 6-2. Measure-Level Gross Realization Rate Estimates for Pipe Insulation 11

Table 7-1. TRC Test Inputs for PGL 12

Table 7-2. TRC Test Inputs for NSG 12

1. INTRODUCTION

This report presents the results of the impact evaluation of the Peoples Gas (PGL) and North Shore Gas (NSG) 2018 Business Prescriptive Program for public sector and commercial and industrial (C&I) customers. It presents a summary of the energy impacts for the total program and broken out by relevant measure and program structure details, for each utility. The appendix presents the impact analysis methodology. The 2018 program covers January 1, 2018 through December 31, 2018.

2. PROGRAM DESCRIPTION

The PGL and NSG comprehensive Business Sector programs bundle offerings into program paths, and allow all eligible C&I and public sector customers to access any of the paths¹ based on the customer's needs. This report covers evaluation activities for measures installed and natural gas savings realized through the Prescriptive Rebate and Energy Jumpstart paths, referred to as the Prescriptive Program in this report. The Prescriptive Rebate path provides standardized incentives for existing commercial and industrial customers and public sector facilities. Standard incentives are based on approximately 50 percent of incremental costs. These incentives focus on heating systems, water heating systems, pipe insulation, steam traps, various boiler controls, food service equipment, and other public sector energy efficiency measures. Franklin Energy Services LLC., (Franklin Energy) is the implementation contractor for the PGL and NSG program, with trade ally engagement and technical support for program delivery and marketing.

The PGL Prescriptive Program had 58 participants in 2018 and completed 142 projects as shown in the following table, including both C&I and public sector prescriptive projects.

Table 2-1. 2018 Volumetric Summary for PGL

| Participation | C&I | Public | Total |
|-------------------------|-----|--------|-------|
| Participants * | 55 | 3 | 58 |
| Installed Projects † | 63 | 79 | 142 |
| Measure Types Installed | 18 | 8 | 18 |

* Participants are defined as number of unique gas account numbers. Public sector participants include school districts that installed projects in multiple buildings.

† Installed Projects are defined as number of unique project IDs

Source: Peoples Gas tracking data and Navigant team analysis.

Table 2-2 summarizes the installed measure quantities that are the basis for PGL verified energy savings.

¹ The comprehensive Business Sector program paths include – Energy Jumpstart (direct installation of free energy saving products), Engineering Studies and staffing assistance, Prescriptive Rebates, Custom Rebates, and Gas Optimization. Only measures that received prescriptive rebates were implemented in 2018; the 2018 program did not realize savings from the Energy Jumpstart path. The custom and gas optimization projects are evaluated and reported separately.

Table 2-2. 2018 Installed Measure Quantities for PGL

| Measure | Quantity Unit | Installed Quantity |
|---|---------------|--------------------|
| C&I | | |
| Boiler Tune Up – Process | MBH | 240,970 |
| Boiler Tune Up – Space Heating | MBH | 314,790 |
| Convection Oven | Each | 2 |
| DCV – Kitchen | HP | 15 |
| High Efficiency Boiler | MBH | 70,726 |
| Linkageless Boiler Controls for Space Heating | MBH | 2,009 |
| Steam Traps – HVAC Repair / Replacement | Each | 723 |
| Steam Traps – Industrial Replacement | Each | 473 |
| Large Gas Water Heater | MBH | 250 |
| Wireless Pneumatic Thermostat (prescriptive change) | Projects | 1 |
| Steam Traps (prescriptive change) | Projects | 6 |
| Public | | |
| Boiler Tune Up – Space Heating | MBH | 858,991 |
| High Efficiency Boiler | MBH | 20,412 |
| Steam Traps – HVAC Repair / Replacement | Each | 83 |
| Steam Traps – Industrial Rep | Each | 46 |
| Steam Traps (prescriptive change) | Projects | 1 |

Source: Peoples Gas tracking data and Navigant team analysis.

The NSG program had 20 participants in 2018 and completed 30 projects as shown in the following table.

Table 2-3. 2018 Volumetric Summary for NSG

| Participation | C&I | Public | Total |
|-------------------------|-----|--------|-------|
| Participants * | 9 | 11 | 20 |
| Installed Projects † | 10 | 20 | 30 |
| Measure Types Installed | 7 | 14 | 18 |

* Participants are defined as number of unique gas account numbers. Public sector participants include school districts that installed projects in multiple buildings.

† Installed Projects are defined as number of unique project IDs

Source: North Shore Gas tracking data and Navigant team analysis.

Table 2-4 summarizes the installed measure quantities that are the basis for NSG verified energy savings.

Table 2-4. 2018 Installed Measure Quantities for NSG

| Measure | Quantity Unit | Installed Quantity |
|--|---------------|--------------------|
| C&I | | |
| Boiler Tune Up – Space Heating | MBH | 65,793 |
| High Efficiency Boiler | MBH | 6,000 |
| Steam Traps – HVAC Repair/Replacement | Each | 15 |
| Steam Traps – Industrial Replacement | Each | 24 |
| Steam Traps (prescriptive change) | Projects | 2 |
| Public | | |
| Boiler Tune Up – Space Heating | MBH | 59,314 |
| High Efficiency Boiler | MBH | 15,210 |
| High Efficiency Furnace > 95% | Each | 5 |
| Pipe Insulation | Linear Feet | 4,882 |
| Steam Traps – HVAC Repair/Replacement | Each | 40 |
| Water Heater 0.67 EF | Each | 1 |
| Furnace > 95% AFUE (prescriptive change) | Projects | 1 |

Source: North Shore Gas tracking data and Navigant team analysis.

3. PROGRAM SAVINGS SUMMARY

Table 3-1 summarizes the energy savings the PGL Prescriptive Program achieved in 2018.

Table 3-1. 2018 Annual Energy Savings Summary for PGL

| Program Path | Ex Ante Gross Savings (Therms) | Verified Gross RR* | Verified Gross Savings (Therms) | NTG† | Verified Net Savings (Therms) |
|-----------------------|--------------------------------|--------------------|---------------------------------|-------------|-------------------------------|
| C&I | 1,811,079 | 100% | 1,811,078 | 0.79 | 1,430,752 |
| Public | 426,263 | 100% | 426,272 | 0.79 | 336,755 |
| PGL Total 2018 | 2,237,342 | 100% | 2,237,350 | 0.79 | 1,767,507 |

* Realization Rate (RR) is the ratio of verified gross savings to ex ante gross savings, based on evaluation research findings.

† Net-to-Gross (NTG) is the ratio of verified net savings to verified gross savings. The NTG ratio is a deemed value. Source:

PGL_and_NSAG_GPY7_NTG_Values_2017-03-01_Faucet Aerator Correction 2019-03-20.xlsx, which is to be found on the Illinois SAG web site: <http://ilsag.info/net-to-gross-framework.html>.

Source: Peoples Gas tracking data and Navigant team analysis.

Table 3-2 summarizes the energy savings the NSG Prescriptive Program achieved in 2018.

Table 3-2. 2018 Annual Energy Savings Summary for NSG

| Program Path | Ex Ante Gross Savings (Therms) | Verified Gross RR* | Verified Gross Savings (Therms) | NTG† | Verified Net Savings (Therms) |
|-----------------------|--------------------------------|--------------------|---------------------------------|-------------|-------------------------------|
| C&I | 235,716 | 100% | 235,713 | 0.79 | 186,213 |
| Public | 79,209 | 107% | 84,961 | 0.79 | 67,119 |
| NSG Total 2018 | 314,925 | 102% | 320,674 | 0.79 | 253,332 |

* Realization Rate (RR) is the ratio of verified gross savings to ex ante gross savings, based on evaluation research findings.

† Net-to-Gross (NTG) is the ratio of verified net savings to verified gross savings. The NTG ratio is a deemed value. Source:

PGL_and_NSAG_GPY7_NTG_Values_2017-03-01_Faucet Aerator Correction 2019-03-20.xlsx, which is to be found on the Illinois SAG web site: <http://ilsag.info/net-to-gross-framework.html>.

Source: North Shore Gas tracking data and Navigant team analysis.

4. PROGRAM SAVINGS BY MEASURE

The PGL program results included 11 Standard Incentive measure categories as shown in the following table. Steam Traps and Boiler Tune Ups contributed the most savings.

Table 4-1. 2018 Annual Energy Savings by Measure for PGL

| Measure Category | Ex Ante Gross Savings (Therms) | Verified Gross RR* | Verified Gross Savings (Therms) | NTG† | Verified Net Savings (Therms) |
|---|--------------------------------|--------------------|---------------------------------|-------------|-------------------------------|
| C&I | | | | | |
| Boiler Tune Up – Process | 201,995 | 100% | 201,990 | 0.79 | 159,572 |
| Boiler Tune Up – Space Heating | 113,141 | 100% | 113,145 | 0.79 | 89,385 |
| Convection Oven | 704 | 100% | 704 | 0.79 | 556 |
| DCV – Kitchen | 11,610 | 100% | 11,610 | 0.79 | 9,172 |
| High Efficiency Boilers | 77,083 | 100% | 77,084 | 0.79 | 60,896 |
| Linkageless Boiler Controls for Space Heating | 1,177 | 100% | 1,175 | 0.79 | 928 |
| Steam Traps – HVAC Repair/Replacement | 222,032 | 100% | 222,032 | 0.79 | 175,405 |
| Steam Traps – Industrial Replacement | 1,055,150 | 100% | 1,055,150 | 0.79 | 833,569 |
| Large Gas Water Heater | 135 | 100% | 135 | 0.79 | 107 |
| Steam Traps (prescriptive change) | 35,577 | 100% | 35,577 | 0.79 | 28,106 |
| Wireless Pneumatic Thermostat (prescriptive change) | 92,475 | 100% | 92,475 | 0.79 | 73,055 |
| C&I Subtotal | 1,811,079 | 100% | 1,811,078 | 0.79 | 1,430,752 |
| Public | | | | | |
| Boiler Tune Up – Space Heating | 308,736 | 100% | 308,748 | 0.79 | 243,911 |
| High Efficiency Boilers | 11,930 | 100% | 11,929 | 0.79 | 9,424 |
| Steam Traps – HVAC Repair/Replacement | 27,189 | 100% | 27,191 | 0.79 | 21,481 |
| Steam Traps – Industrial Replacement | 75,675 | 100% | 75,672 | 0.79 | 59,781 |
| Steam Traps (prescriptive change) | 2,732 | 100% | 2,732 | 0.79 | 2,158 |
| Public Subtotal | 426,263 | 100% | 426,272 | 0.79 | 336,755 |
| PGL TOTAL 2018 | 2,237,342 | 100% | 2,237,350 | 0.79 | 1,767,507 |

* Realization Rate (RR) is the ratio of verified gross savings to ex ante gross savings, based on evaluation research findings.

† Net-to-Gross (NTG) is the ratio of verified net savings to verified gross savings. The NTG ratio is a deemed value. Source:

PGL_and_NSAG_GPY7_NTG_Values_2017-03-01_Faucet Aerator Correction 2019-03-20.xlsx, which is to be found on the Illinois SAG web site: <http://ilsag.info/net-to-gross-framework.html>.

Source: Peoples Gas tracking data and Navigant team analysis.

The NSG program results included 9 measures as shown in the following table.

Table 4-2. 2018 Annual Energy Savings by Measure for NSG

| Measure Category | Ex Ante Gross Savings (Therms) | Verified Gross RR* | Verified Gross Savings (Therms) | NTG† | Verified Net Savings (Therms) |
|--|--------------------------------|--------------------|---------------------------------|-------------|-------------------------------|
| C&I | | | | | |
| Boiler Tune Up – Space Heating | 23,647 | 100% | 23,648 | 0.79 | 18,682 |
| High Efficiency Boilers | 6,756 | 100% | 6,757 | 0.79 | 5,338 |
| Steam Traps – HVAC Repair/Replacement | 4,914 | 100% | 4,914 | 0.79 | 3,882 |
| Steam Traps – Industrial Replacement | 50,279 | 100% | 50,274 | 0.79 | 39,716 |
| Steam Traps (prescriptive change) | 150,120 | 100% | 150,120 | 0.79 | 118,595 |
| C&I Subtotal | 235,716 | 100% | 235,713 | 0.79 | 186,213 |
| Public | | | | | |
| Boiler Tune Up – Space Heating | 21,318 | 100% | 21,319 | 0.79 | 16,842 |
| High Efficiency Boilers | 17,128 | 100% | 17,128 | 0.79 | 13,531 |
| High Efficiency Furnace > 95% | 1,133 | 100% | 1,133 | 0.79 | 895 |
| Pipe Insulation | 25,462 | 123% | 31,213 | 0.79 | 24,659 |
| Steam Traps – HVAC Repair/Replacement | 13,103 | 100% | 13,104 | 0.79 | 10,352 |
| Water Heater 0.67 EF | 35 | 100% | 35 | 0.79 | 28 |
| Furnace > 95% AFUE (prescriptive change) | 1,029 | 100% | 1,029 | 0.79 | 813 |
| Public Subtotal | 79,209 | 107% | 84,961 | 0.79 | 67,119 |
| NSG TOTAL 2018 | 314,925 | 102% | 320,674 | 0.79 | 253,332 |

* Realization Rate (RR) is the ratio of verified gross savings to ex ante gross savings, based on evaluation research findings.

† Net-to-Gross (NTG) is the ratio of verified net savings to verified gross savings. The NTG ratio is a deemed value. Source: PGL_and_NSg_GPY7_NTG_Values_2017-03-01_Faucet Aerator Correction 2019-03-20.xlsx, which is to be found on the Illinois SAG web site: <http://ilsag.info/net-to-gross-framework.html>.

Source: North Shore Gas tracking data and Navigant team analysis

5. IMPACT ANALYSIS FINDINGS AND RECOMMENDATIONS

5.1 Impact Parameter Estimates

Table 5-1 shows the unit therm savings and realization rate findings by measure. The realization rate is the ratio of the verified gross savings to the ex ante gross savings. Following the table, we provide findings and recommendations, including discussion of all measures with realization rates above or below 100 percent. Appendix 1 provides a description of the impact analysis methodology.

Table 5-1. Verified Gross Savings Parameters

| Measure | Unit Basis | Ex Ante Gross (Therms/unit) | Verified Gross (Therms/unit) | RR | Data Source(s) |
|---|------------|------------------------------|------------------------------|------|---------------------------------------|
| Boiler Tune Up - Process | MBH | 0.838 | 0.838 | 100% | IL TRM v6.0*, Section 4.4.3 |
| Boiler Tune Up - Space Heating | MBH | 0.359 | 0.359 | 100% | IL TRM v6.0, Section 4.4.2 |
| Convection Oven | Each | 352 | 352 | 100% | IL TRM v6.0, Section 4.2.5 |
| DCV - Kitchen | HP | 774 | 774 | 100% | IL TRM v6.0, Section 4.2.16 |
| Boiler - HW >=300MBtu, >88% TE | MBH | 1.126 | 1.126 | 100% | IL TRM v6.0, Section 4.2.10 |
| Boiler - Steam >=1500MBH, >=82% TE | MBH | 0.991 | 0.991 | 100% | IL TRM v6.0, Section 4.2.10 |
| Linkageless Boiler Controls for Space Heating | MBH | 0.586 | 0.586 | 100% | IL TRM v6.0, Section 4.4.21 |
| Steam Traps - HVAC Repair/Rep | Each | Audit = 328 No Audit = 88 | Verified | 100% | IL TRM v6.0, Section 4.4.16 |
| Steam Traps - Industrial Rep* | Each | Vary | Verified | 100% | IL TRM v6.0, Section 4.4.16 |
| Large Gas Water Heater | MBH | 0.54 | 0.54 | 100% | IL TRM v6.0, Section 4.3.1 |
| High Efficiency Furnace | Each | 227 | 227 | 100% | IL TRM v6.0, Section 4.2.11 |
| Pipe Insulation† | Ln Ft. | Vary | Verified. Adjusted | 107% | IL TRM v6.0, Section 4.4.16‡ MMDB§ |
| Water Heater 0.67 EF | Each | 35.43 | 35.436 | 100% | IL TRM v6.0, Section 4.3.1 |
| Other (Prescriptive Change) | Projects | Vary | Verified as acceptable | 100% | MMDB§ |

* There are multiple subsets of industrial steam trap types (i.e. different psig ranges). Details of measure type and savings are shown below

† There are multiple subsets of pipe insulation (i.e. different diameter ranges). Details of measure type and savings are shown below.

‡ State of Illinois Technical Reference Manual version 6.0 from <http://www.ilsag.info/technical-reference-manual.html>.

§ Franklin Energy's Master Measure Database spreadsheet, Commercial PG NSG MMDB PY7 2018-08-09.

Source: Program Tracking Data (PTD) provided by Peoples Gas and North Shore Gas, extract dated February 4, 2019.

5.2 Other Findings and Recommendations

Pipe Insulation

Navigant found that the tracked ex ante gross therms savings for pipe insulation were equivalent to the MMDB values. The verified savings however are different from the MMBD primarily due to inconsistencies in formulas in the MMDB file. Formulas in the same column referenced inconsistent cells for what should be the same equation. There were some references to cells in an incorrect column and other cases where certain values were double counted. In the case of Steam Small 1" to 2" and Medium 2.1" to 5" the

formulas referenced condensate therm/ft instead of steam. These errors lead to the higher realization rates for some of the pipe insulation measures, resulting in 107 percent overall gross realization rate.

Recommendation 1: The MMDB should be reviewed to ensure that formulas in the same column do not reference different cells for what should be the same equation. There were other cases where certain values were double counted or averaged. In the case of Steam Small 1” to 2” and Medium 2.1” to 5”, the formulas referencing condensate nominal therm/ft should instead all be steam nominal therms/ft. For fittings and valves, (e.g. Steam Med Fitting 2.1” to 5”), check the formula to avoid double calculating the savings for 5” fitting sizes.

Boiler HW

The ex ante gross therms savings for Hot Water (HW) Boiler were equivalent to the MMDB values. However, the ex ante savings assumes a conservative baseline efficiency assumption of 82% for all HW Boilers ≥ 300 MBTU. In the TRM, HW Boilers ≥ 300 MBTU & $\leq 2,500$ MBH have a baseline efficiency of 80%, and the HW Boilers $> 2,500$ MBH have a baseline of 82%. Navigant’s impact evaluation approach follows the TRM for this measure, so verified savings for the ≥ 300 MBTU & $\leq 2,500$ MBH category are based on a baseline efficiency of 80%. In 2018, there were no installations of HW Boilers ≥ 300 MBTU & $\leq 2,500$ MBH, but we expect there could be installations in 2019.

Recommendation 2: To match the evaluation approach for estimating savings, the MMDB and tracking system should use a baseline efficiency of 80% for HW Boilers ≥ 300 MBTU & $\leq 2,500$ MBH, and a baseline efficiency of 82% for HW Boilers $> 2,500$ MBH. Franklin Energy could consider updating the MMDB and tracking system to track these boiler sizes separately due to the differences in the baseline efficiencies, based on the TRM.

Storage Water Heater

Navigant found that in calculating the hot water usage for the large water heater, the ex ante estimate used the average consumption per capacity across all building types (576.8 consumption/cap). Similarly, for the “Water Heater 0.67 EF” measure, the custom value was 558 consumption/cap. The evaluation team did not adjust these values, but recommend using deemed values by project or building type.

Recommendation 3: Navigant recommends that the consumption/cap assumption for calculating the hot water usage in gallons be based on project-specific data and use the corresponding deemed building type values.

Prescriptive Change Projects

Navigant identified eleven “prescriptive change” projects in the tracking system.² These comprised of seven PGL industrial steam trap projects and one wireless pneumatic thermostat and two NSG industrial steam trap projects and one furnace project. We reviewed the prescriptive approach and the savings inputs and agreed that the savings cap at 20 percent of gas usage was reasonable. We did not adjust the savings any further and maintained a 100 percent gross realization rate.

Historical Results

Table 5-2 below shows the historical gross realization rates and NTG values for the C&I Prescriptive Program. Table 5-3 below shows the historical gross realization rates and NTG values for the Public

² Using the TRM assumptions for these projects produced significantly more savings but the results were inconsistent with the nature of the projects. As a result, Franklin Energy capped the savings at 20 percent of the account’s annual gas usage.

Sector Prescriptive Program, beginning with GPY6 when PGL and NSG assumed administration of the program.

Table 5-2. Historical Realization Rates and NTG Values – C&I

| Program Year | PGL Verified Gross RR | NSG Verified Gross RR | PGL NTG | NSG NTG |
|--------------|-----------------------|-----------------------|---------|---------|
| GPY1 | 100% | 100% | 0.43 | 0.43 |
| GPY2 | 100% | 100% | 0.63 | 0.63 |
| GPY3 | 100% | 100% | 0.63 | 0.63 |
| GPY4 | 100% | 100% | 0.58 | 0.58 |
| GPY5 | 99% | 100% | 0.63 | 0.63 |
| GPY6 | 100% | 100% | 0.79 | 0.79 |
| 2018 | 100% | 100% | 0.79 | 0.79 |

Source: Navigant evaluation research.

Table 5-3. Historical Realization Rates and NTG Values – Public Sector

| Program Year | PGL Verified Gross RR | NSG Verified Gross RR | PGL NTG | NSG NTG |
|--------------|-----------------------|-----------------------|---------|---------|
| GPY6 | 100% | 100% | 0.54 | 0.51 |
| 2018 | 100% | 107% | 0.79 | 0.79 |

Source: Navigant evaluation research.

6. APPENDIX 1. IMPACT ANALYSIS METHODOLOGY

Navigant compared the savings calculation method in the 2018 tracking data to Franklin Energy’s “Master Measure Database” file (MMDB)³, which feeds into calculating the tracking data savings, and to IL TRM-based savings values. Navigant verified that the IL TRM algorithms were correctly applied in the MMDB. Navigant checked that measure inputs matched deemed IL TRM inputs and validated custom inputs. To be eligible, an IL TRM measure must meet the physical, operational, and baseline characteristics as defined in the applicable version of the IL TRM.⁴

Navigant reviewed the program tracking data drawn from a February 4, 2019 extract to substantiate the type and quantity of measures installed. Verified gross realization rates are calculated by dividing the verified gross savings by the ex ante gross savings.

The deemed savings verification approach was supplemented by engineering file review of nine prescriptive projects that were described as “prescriptive change” in the tracking data. Navigant verified these measures were mostly steam traps and that the program claimed savings based on 20 percent of gas usage. We determined that the savings reported for these projects are reasonable and therefore estimated 100 percent gross realization rate for these projects.

Steam Traps

Below is the measure level detail for industrial steam trap measures. The program tracking database is now providing more details of the pressure size and steam trap types being installed. This additional detail is responsive to Navigant’s recommendation from the previous program year. There were no adjustments to savings.

Table 6-1. Measure-Level Gross Realization Rate Estimates for Steam Traps

| Measure | Quantity Installed | Quantity Unit | Ex Ante Unit Therms Savings | Verified Unit Therms Savings | Gross Therms Realization Rate (RR) |
|--|--------------------|---------------|------------------------------|------------------------------|------------------------------------|
| Steam Traps - HVAC Repair/Rep | 861 | Each | Audit = 328 No Audit = 88 | Verified | 100% |
| Steam Traps - Industrial/Process Audit - psig <= 15 | 268 | Each | 673 | 673 | 100% |
| Steam Traps - Industrial/Process Audit - 15 < psig < 30 | 24 | Each | 630 | 630 | 100% |
| Steam Traps - Industrial/Process Audit - 30 <= psig < 75 | 58 | Each | 2,197 | 2,197 | 100% |
| Steam Traps - Industrial/Process Audit - 75 <= psig < 125 | 132 | Each | 3,956 | 3,956 | 100% |
| Steam Traps - Industrial/Process Audit - 125 <= psig < 175 | 56 | Each | 5,369 | 5,369 | 100% |
| Steam Traps - Industrial/Process Audit - 175 <= psig < 250 | 5 | Each | 7,052 | 7,052 | 100% |

* Quantities shown combines PGL and NSG.
Source: Navigant analysis of tracking data.

³ File name: COMMERCIAL PG NSG MMDB PY7 2018-08-09, produced by Franklin Energy.

⁴ Illinois Statewide Technical Reference Manual for Energy Efficiency Version 6.0 from <http://www.ilsag.info/technical-reference-manual.html>

Pipe Insulation

Below are the per unit savings estimate for pipe insulation and pipe fittings. Further discussion and recommendations on the evaluation adjustment are provided in Section 5.

Table 6-2. Measure-Level Gross Realization Rate Estimates for Pipe Insulation

| Measure | Quantity Installed* | Quantity Unit | Ex Ante Unit Therms Savings | Verified Unit Therms Savings | Gross Therms Realization Rate (RR) | Evaluation Adjustment |
|--|---------------------|---------------|-----------------------------|------------------------------|------------------------------------|---|
| Pipe Insulation - Steam Med Fitting | 72 | Ln. ft | 11.69 | 14.38 | 123% | Removed double averaging fitting size 5" |
| Pipe Insulation - Steam Large Fitting | 25 | Ln. ft | 44.89 | 40.66 | 91% | Removed double averaging fitting sizes 6-8" |
| Pipe Insulation - HW Small 1" to 2" | 983 | Ln. ft | 2.66 | 2.66 | 100% | OK |
| Pipe Insulation - HW Medium 2.1" to 4" | 1,890 | Ln. ft | 5.25 | 5.68 | 108% | Corrected error in averaging nominal therms/ft |
| Pipe Insulation - Steam Small 1" to 2" | 1,331 | Ln. ft | 3.19 | 5.64 | 177% | Corrected condensate nominal therms/ft to steam |
| Pipe Insulation - Steam Med 2.1" to 5" | 521 | Ln. ft | 9.78 | 12.81 | 131% | Corrected condensate nominal therms/ft to steam |
| Pipe Insulation - Steam Large 5.1" to 8" | 48 | Ln. ft | 25.00 | 25.00 | 100% | OK |
| Pipe Insulation - Steam X-Large >8" | 12 | Ln. ft | 35.98 | 35.98 | 100% | OK |

* Quantities shown combine PGL and NSG.
 Source: Navigant analysis of tracking data.

Navigant calculated verified net energy savings by multiplying the verified gross savings estimates by a net-to-gross ratio (NTG). In 2018, the NTG estimates used to calculate the net verified savings were based on past evaluation research and defined by a consensus process through SAG, as documented in a spreadsheet.⁵

⁵ Source: PGL_and_NSQ_GPY7_NTG_Values_2017-03-01_Faucet Aerator Correction 2019-03-20.xlsx, which is to be found on the IL SAG web site here: <http://ilsag.info/net-to-gross-framework.html>.

7. APPENDIX 2. PROGRAM-SPECIFIC INPUTS FOR THE ILLINOIS TRC

Table 7-1 and Table 7-2, the Total Resource Cost (TRC) variable tables, only include cost-effectiveness analysis inputs available at the time of finalizing the 2018 Prescriptive Program impact evaluation report. Additional required cost data (e.g., measure costs, program level incentive and non-incentive costs) are not included in the tables and will be provided to the evaluation team later. Detail in the TRC tables (e.g., EULs), other than final 2018 savings and program data, are subject to change and are not final.

Table 7-1. TRC Test Inputs for PGL

| Measure | Units | Quantity | Effective Useful Life | Ex Ante Gross Savings (Therms) | Verified Gross Savings (Therms) | Verified Net Savings (Therms) |
|---|---------|-----------|-----------------------|--------------------------------|---------------------------------|-------------------------------|
| Boiler Tune Up - Process | MBH | 240,970 | 3.0 | 201,995 | 201,990 | 159,572 |
| Boiler Tune Up - Space Heating | MBH | 1,173,781 | 3.0 | 421,877 | 421,893 | 333,295 |
| Convection Oven | Each | 2 | 12.0 | 704 | 704 | 556 |
| DCV - Kitchen | HP | 15 | 15.0 | 11,610 | 11,610 | 9,172 |
| High Efficiency Boiler | MBH | 91,138 | 20.0 | 89,013 | 89,013 | 70,320 |
| Linkageless Boiler Controls for Space Heating | MBH | 2,009 | 16.0 | 1,177 | 1,175 | 928 |
| Steam Traps - HVAC Repair/Rep | Each | 806 | 6.0 | 249,221 | 249,223 | 196,886 |
| Steam Traps - Industrial Rep | Each | 519 | 6.0 | 1,130,825 | 1,130,822 | 893,349 |
| Large Gas Water Heater | MBH | 250 | 15.0 | 135 | 135 | 107 |
| Wireless Pneumatic Thermostat (prescriptive change) | Project | 1 | 4.0 | 92,475 | 92,475 | 73,055 |
| Steam Trap (prescriptive change) | Project | 7 | 6.0 | 38,309 | 38,309 | 30,264 |
| PGL Total 2018 | | | 5.7 | 2,237,342 | 2,237,350 | 1,767,507 |

Source: Program Tracking Data (PTD) provided by Peoples Gas and North Shore Gas, extract dated February 4, 2019.

Table 7-2. TRC Test Inputs for NSG

| Measure | Units | Quantity | Effective Useful Life | Ex Ante Gross Savings (Therms) | Verified Gross Savings (Therms) | Verified Net Savings (Therms) |
|--|---------|----------|-----------------------|--------------------------------|---------------------------------|-------------------------------|
| Boiler Tune Up - Space Heating | MBH | 125,107 | 3.0 | 44,965 | 44,967 | 35,524 |
| High Efficiency Boiler | MBH | 21,210 | 20.0 | 23,884 | 23,885 | 18,869 |
| Steam Traps - HVAC Repair/Rep | Each | 55 | 6.0 | 18,017 | 18,018 | 14,234 |
| Steam Traps - Industrial Rep | Each | 24 | 6.0 | 50,279 | 50,274 | 39,716 |
| High Efficiency Furnace | Each | 5 | 17.0 | 1,133 | 1,133 | 895 |
| Pipe Insulation | Ln Ft. | 4,882 | 15.0 | 25,462 | 31,213 | 24,658 |
| Water Heater 0.67 EF | Each | 1 | 15.0 | 35 | 35 | 28 |
| Furnace > 95% AFUE (prescriptive change) | Project | 1 | 17.0 | 1,029 | 1,029 | 813 |
| Steam Trap (prescriptive change) | Project | 1 | 6.0 | 150,120 | 150,120 | 118,595 |
| NSG TOTAL 2018 | | | 7.6 | 314,924 | 320,674 | 253,332 |

Source: Program Tracking Data (PTD) provided by Peoples Gas and North Shore Gas, extract dated February 4, 2019.